

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Marquette COUNTY


T 46 N R 26 W

DESCRIPTION OF CORNER Section corner for sections ^{28/27} 33/34

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/27/70

WITNESSES TO CORNER..... 7" J. Pine (S.28) (NBT) N 43° W, 35.3'



10" J. Pine (S. 34) (NBT) S 86° E, 50.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Set by double proportionate measurement (between section corners 1 mile to E & W - N & S). Checks well with streams west and south, swamp edge north. No evidence of original corner found. Few old blazes in area of corner. Old trapper passing said he remembers corner in vicinity.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

11/20/70

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68