

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 1 Marquette

| Located In: | Corner Code # |
|-----------------------------------|---------------|
| 1. Public Land Survey T 46N R 26W | J7 |
| T R | |
| T R | |
| T R | |
| 2. Property Controlling S 23 T R | 1 |
| S T R | 3 |
| 3. Miscellaneous S T R | 8 |
| Property in Sec. S T R | |

Register of Deeds Stamp & File Number

4 Lot No _____, Recorded Plat _____
 5 Private Claims _____

I, Keith Sackett, in a field survey on August 9, 1990, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereto as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 13 | 14 | 15 | 16 | 17 | 18 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 25 | 26 | 27 | 28 | 29 | 30 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A Description of original monument and accessories and/or subsequent restoration:

| J7 | 1 | 3 | 8 |
|--|--|--|--|
| Original monument and accessories not found. | Not set on original survey nor subsequently, apparently. | Not set on original survey nor subsequently, apparently. | Not set on original survey nor subsequently, apparently. |

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

| J7 | 1 | 3 | 8 |
|------------------------------|---------------------------------|---------------------------------|---------------------------------|
| Restored midway and on line. | Established midway and on line. | Established midway and on line. | Established midway and on line. |

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| J7 | 1 | 3 | 8 |
|---|---|---|---|
| Set 1" ID x 7/2" iron pipe w/4" aluminum cap. | Set 1" ID x 3/2" iron pipe w/4" aluminum cap. | Set 1" ID x 3/2" iron pipe w/4" aluminum cap. | Set 1" ID x 3/2" iron pipe w/4" aluminum cap. |
| 28" v. pine N87W 150.1' 1/4s NBT | 8" oak N30W 18.4' 1/16s BT | 8" spruce S63E 24.0' 1/16s BT | 5" v. pine N35W 7.3' 1/16s BT |
| 8" maple N77E 45.2' 1/4s NBT | 4" oak S38E 15.7' 1/16s BT | 6" maple N34W 29.2' 1/16s BT | 5" maple S30W 13.8' 1/16s BT |
| 7" spruce S48W 45.3' 1/4s NBT | 8" oak S36W 28.2' 1/16s BT | 5" maple S72W 21.4' 1/16s BT | 5" maple N85E 16.3' 1/16s BT |

Signed by Keith Sackett Date August 24, 1990

Surveyor's Michigan License No. _____

19006

