

1999 DEC 22 AM 11:24

Patricia A. Monahan
REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 46N R 25W A-2 ✓
T 46N R 26W M-2 ✓
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER **R2** PAGE 194

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on October 27th, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-2: Corner common to Section 6, T46N-R25W and Section 1, T46N-R26W.
1844: William A. Burt's original township boundary survey notes describe the corner monument as a 5" S. Pine referenced by:
8" S. Pine S50W, 29L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2: 1999: No original corner evidence found. Corner was set by single proportionate measurement on line between the Township corner to the North and the Southwest corner of Section 6. The distance North is 2663.79' and the distance South is 2640.03'. There were no distinctive line calls to measure to.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2: 1999: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.1' above ground. Referenced by:
15" Jack Pine N25E, 12.69' 5" Jack Pine S64E, 21.35'
13" Jack Pine S18E, 67.96' 12" Jack Pine N90W, 5.42'
Green Steel Sign Post w/ Yellow Survey Marker Sign N30W, 2.55'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 12, Pg. 98 Bk.15, Pg. 5-8 Corner Search Report 99100
Bk. 15, Pg. 11-12

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP
P.A. 345 OF 1999

Larry J. Buason
DATE 10/25/99



Signed by Gerald W. Carlson Date 12-8-99

Surveyor's Michigan License No. 24589