

1999 DEC 22 AM 11:24

Patricia A. Monley
REGISTER OF DEEDS
pm

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 46N R 25W A-4
T 46N R 26W M-4 ✓
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER **R2** PAGE 196

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on May 12, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A-4: Corner common to Sections 7, T46N-R25W and 12, T46N-R26W

1844: William A. Burt's original township boundary survey notes describe the corner monument as a wood post referenced by:
5" S. Pine S39E, 17L 4" S. Pine N58W, 11L

No Date: Cleveland Cliffs coordinate data sheets, indicate the corner is distance N00-24-59E, 2636.16' to the Northwest section corner and distance S00-23-58W, 2652.58' to the Southwest corner of Section 7, T45N-R25W. No monument description or references given.

1951: A Land Corner Record by Dean Delameter, P.S. #5778 of the Michigan Department of Conservation, indicates their Forestry Division survey crew set a 1" pipe with a 4" brass cap. Delameter states: "This Corner was established by the Forestry Division survey crew, while making a partial resurvey of this area. Corner was placed and witnessed September 4, 1951." The following references were given:

8" Jack Pine S06E, 22L 8" Jack Pine N40E, 19L

No Date: Marquette County Road Commission notes indicate the corner monument is a 1" pipe with a 4" brass cap with the following references:

8" Jack Pine S06E, 22L 8" Jack Pine N40E, 19L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4: 1999: No original corner evidence found. Found and accepted a 1 1/4" outside diameter iron pipe with a 4" brass tablet projecting 1.6' above ground and stamped for identification. No department of Conservation References were found. Distance North is 2636.02', South is 2652.29'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4: 1999: Stamped the 1 1/4" outside diameter iron pipe with brass 4" monument with: "MCR 1999" and drove it further into the ground so it now projects 0.85' above ground and is stable.

Established new references:

7" Jack Pine S27E, 73.77' 6" Jack Pine S62E, 137.82'
10" Jack Pine S84E, 163.17' 5" Jack Pine N45E, 63.05'
+/- 150' West of North-South dirt road.

Green Steel Sign Post w/ Yellow Survey Marker Sign N77W, 4.05'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

T46N-R25W Corner Search Report 99100

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP:
P.A. 345 OF 1990

Larry J. Burrage
DATE 10/25/99



Signed by Gerald W. Carlson

Date 12-8-99

Surveyor's Michigan License No. 24589