

1999 DEC 22 AM 11: 24

Patricia A. Manley
REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 46N R 25W A-6 ✓
T 46N R 26W M-6 ✓
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER **R2** PAGE 198

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on May 18, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6: Corner common to Sections 18, T46N-R25W and 13, T46N-R26W.

1844: William A. Burt's original township boundary survey notes describe the corner monument as a wood post referenced by:

14" W. Pine S63W, 30L 18" W. Pine N20E, 31L

1953: A Land Corner Record by the Michigan Department of Conservation-Forestry

Division, indicates a 1" pipe with 4" brass cap was set. The Land Corner Record states: "this corner was pointed out to me by Arne Metsa, District Forester, of Gwinn Twp. original B.T.'s

still in place, one in good condition, one fair. Corner was placed and witnessed November 10, 1953." The following references were given:

12" W. Pine S15W, 4L 12" W. Pine N38W, 14L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6: 1999: No original corner evidence found. Found and accepted a 1 1/4" outside diameter iron pipe with a 4" brass tablet projecting 1.5' above ground.

Checked Line Call: South, 1 chain (66'), Valley height 535.1 ft. We measured 66' to the center of a small valley.

Checked Line Call: South, 10.5 chains(693') , granite knob. We measured 625' to the granite knob.

Checked Line Call: South, 19.67 chains(1298.2'), Over River/ Rock Bottom. We measured 1252'.

Distance North is 2518.97, South is 2625.62'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6: 1999: Stamped the 1 1/4" outside diameter iron pipe with a 4" brass tablet monument with: "MCR 1999". We referenced the monument and dug it out of the ground. The pipe is 3.0' in length with an anchor 8" from the bottom. We reset the monument so it now projects 1.0' above the ground.

Green Steel Sign Post w/ Yellow Survey Marker Sign N06E, 3.11'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 12 , Pg. 110-111 T46N-R25W Corner Search Report 99100

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6	●	18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

RATIFIED BY PERM
P.A. 345 OF 1990

Gerald W. Carlson
DATE 10/25/99



Signed by *Gerald W. Carlson*

Date 12-8-99

Surveyor's Michigan License No. 24589