

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 NR. 27 W.

Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 21, 22, 27, and 28

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 9" Jack Pine (S 22 NBT) N 60° E 05 Links

12" Jack Pine (S 21 NBT) N 70° W 43 Links

11" Jack Pine (S 28 NBT) S 64° W 38 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one White Pine bearing tree, bearing N 23° E 31 Links

Tree fallen down and in poor condition. Found several scribe marks on upper face.

Corner found by chaining from streams and hills as recorded in Government notes.

Corner was placed and witnessed April 20, 1960 with Frank J. Bray and G. Ellis.

SURVEYORS SEAL

SIGNED

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 5/18/60