

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 46, NR. 27 W

Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 15 and 22

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 8" Sugar Maple (1/4s NBT) S 34° W 08 Links

7" Sugar Maple (1/4s NBT) N 68° E 10 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two probable bearing trees, N 12° W 25 Links and S 71° E 35 Links. Found part of face with overgrowth and possible scribe marks on SE B.T. Position fits swamp edge to east and corners to west.

Corner was placed and witnessed April 20, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

*Billy D. Buckler*  
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 5/18/60