

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46. NR. 27. W

Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 14, 15, 22, 23.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 15" W. Pine (S 23 NBT) S 21° E 09 Links

15" W. Pine (S 14 NBT) N 23° E 61 Links

14" W. Pine (S 15 NBT) N 40° W 93 Links

13" R. Pine (S 22 NBT) S 32° W 115 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one W. Pine B.T. bearing N 24° W 15 Links. Tree down and in poor condition. Found notch on lower blaze and upper face with overgrowth. Numerous blazes at corner. Found wood post at corner.

Corner was placed and witnessed May 5, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED *Billy D. Buckler* DATE 5/23/60
REGISTERED LAND SURVEYOR
Billy D. Buckler