

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 .. NR .. 22 .. W

Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 15, 16, 21, 22 ..

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 6" Soft Maple .. (NBT) .. S 17° W .. 19 Links

5" Soft Maple .. (S 16 NBT) .. N 70° W .. 48 Links

5" Soft Maple .. (S 15 NBT) .. N 19° E .. 20 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED. This corner was replaced from one W. Pine Stump bottom in proper position.
Located by proportionate dist. from corners east, west and south and stream to north.

Corner was placed and witnessed August 22, 1960 wit C. Schooley, D.F.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE 8-29-60 ..