

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 . . NR . . 22 . . W

. M a r q u e t t e . . . . . COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 28 and 33

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 24" W. Pine (1/4s NBT) N 57° E 10 Links

20" W. Pine (1/4s NBT) S 14° E 29 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced from a W. Pine Stump bearing S 19° W , 26 Links Stump in poor condition, found notches and a Y. Pine bearing N 71° E , 20 Links. Stump in poor condition. Position checks with marsh to west.

Corner was placed and witnessed August 22, 1960 with C. Schooley, D.F..

SURVEYORS SEAL

SIGNED

*Billy D. Buckler*  
REGISTERED LAND SURVEYOR

DATE 8-29-60

Billy D. Buckler