

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46. NR. 27. W

Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 16, 17, 20, 21

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 12" Tamarack (S 17 NBT) N 74° W 68 Links

8" J. Pine (S 16 NBT) N 55° E 116 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced from possible B.T. a pine bearing N 22° W 43 Links. Hills to north, east and west check. Found old blazes on down Y. Pine North and west of corner. Corner lies in a wet marsh.

Corner was placed and witnessed August 22, 1960 with C. Schooley.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 9/13/60
REGISTERED LAND SURVEYOR
Billy D. Buckler