

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N. R. 27W


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 28-29-32-33

CORNER MONUMENT 1" Pipe with 4" Aluminum Pipe

DATE MONUMENT PLACED AND WITNESSED 6/15/67

WITNESSES TO CORNER..... 8" Soft Maple (S33 NBT) S20°E 33.8'



8" Hard Maple (S28 NBT) N17°E 24.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by proportionate measure from Corners 1 mile West and 1/2 mile East, and on an old line of blazes East & West. Distance South, 1/2 mile to an original Corner checks well.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 10/25/67
REGISTERED LAND SURVEYOR