

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 46 N.R. 27W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 19-30

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/15/67

WITNESSES TO CORNER..... 9" Jack Pine (1/4S NET) N34°E 54.6'



9" Jack Pine (1/4S NET) N34°E 42.9'

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner re-established by single proportionate measure and on line between two Section Corners.  
Found no evidence of Original Corners.

Corner lies  $2\frac{1}{2}$  chains west of a woods road and  $\frac{1}{2}$  chain south of a recent cutting edge, in Jack Pine slash.

**SURVEYOR'S SEAL**

SIGNED Billy D. Buckler DATE 10/25/67  
Billy D. Buckler  
REGISTERED LAND SURVEYOR