

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 27W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 20-29

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 5/16/67

WITNESSES TO CORNER..... 9" Jack Pine (1/4S NBT) N44°E 89.4'



9" Jack Pine (1/4S NBT) S85°E 59.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from remains of one original witness; a W. Pine bearing N42°E, 18 links, tree down, burned and rotted with axe marks and part of lower face in evidence. Found stump bottom bearing S34°W 07 Links.

Corner lies on an open hillside, facing to South.

Found no evidence of use.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 10/25/67
REGISTERED LAND SURVEYOR