

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 27W


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19-20-29-30

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 5/31/67

WITNESSES TO CORNER..... 12" Jack Pine (S20 NBT) N27°E 3.3'



6" Jack Pine (S19 NBT) N10°W 38.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by Double Proportionate measure from Corners in all four directions. Corner also lies on a straight line between Corner 1 mile West and 1/2 mile East.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR
DATE 10/25/67