

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 26-27 W.


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 25, 36, 30, and 31

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 10-15-62

WITNESSES TO CORNER..... 7" Jack Pine (S. 30 N.B.T.) N. 18° E., 56 Lks.



9" Jack Pine (S. 25 N.B.T.) N. 55° W., 38 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner placed at end of fence from North. Found old squared Jack Pine (down) at fence with 1½" Iron Pipe set by unknown surveyor. Corner found by Forestry Division Survey Crew.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE _____
REGISTERED LAND SURVEYOR