

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE COUNTY

| FOR CORNERS OF --: | LOCATED IN --: | CORNER CODE NUMBER |
|---------------------------------------|--------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 46 N. X R. 27 W. | J12 |
| 2. PROPERTY CONTROLLING IN SECTION 35 | T. 46 N. X R. 27 W. | 11, 8 |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. S. R. E. W. | |
| 4. LOT NO., RECORDED PLAT | | |
| 5. PRIVATE CLAIMS | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner J12: Not set on original survey nor subsequently apparently.
- Corner 11: Not set on original survey nor subsequently apparently.
- Corner 8: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner J12: Established 9-3-82 during section subdivision.
- Corner 11: Established 9-3-82 during section subdivision.
- Corner 8: Established 9-2-82 during section subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| Corner J12: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap. 6" Maple S18W 12.5 ft. 1/4S, BT 7" W. Birch N52W 13.6 ft. 1/4S, BT 9" J. Pine N01E 20.0 ft. 1/4S, BT | Corner 8: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap. 16" J. Pine S45E 14.8 ft. 1/16S, BT 12" W. Pine S37W 34.9 ft. 1/16S, BT 14" J. Pine N52W 10.1 ft. 1/16S, BT |
| Corner 11: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap. 4" R. Pine N12W 36.2 ft. 1/16S, BT 8" R. Pine N64E 44.7 ft. 1/16S, BT 5" W. Birch S50E 19.1 ft. 1/16S, BT | |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2-16-83
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

