

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE COUNTY

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY...	T. 46N. <del>S.</del> N. R. 27. <del>E.</del> W.	I11, K11, I12
2. PROPERTY CONTROLLING IN SECTION	T. .... N. S. R. .... E. W.	-----
3. MISCELLANEOUS PROPERTY IN SECTION	T. .... N. S. R. .... E. W.	-----
4. LOT NO. ...., RECORDED PLAT .....	-----	-----
5. PRIVATE CLAIMS .....	-----	-----

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-31- 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I11: Found old post with two stumps matching original species, bearings, and approximate distances. Found original line tree south.

Corner K11: Original monument and accessories not found. Found old down post set by unknown person.

Corner I12: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I11: Restored at old post.

Corner K11: Restored at old post. Location checks good with other corners.

Corner I12: Restored midway and on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I11: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap. 12" oak N70W 4.7 ft. S27, NBT 7" Maple S31E 14.0 ft S35, NBT 10" W. Birch N60E 17.6 ft, S26, NBT	Corner I12: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap. 8" Oak S53E 24.4 ft. 1/4S, NBT 10" Oak N42E 34.6 ft 1/4S, NBT 4" Maple N55W 12.3 ft. 1/4S, NBT
--	--

Corner K11: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.  
 4" R. Pine N79W 9.7 ft. S26, NBT  
 3" R. Pine S29W 16.6 ft. S35, NBT  
 5" J. Pine S55E 12.0 ft. S36, NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 2-16-83

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
**Keith L. Sackett**  
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

