

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 46 N. R. 27 X. W.	K12, J11
2. PROPERTY CONTROLLING IN SECTION.....	35 T. 46 N. R. 27 X. W.	9
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. S. R. E. W.	
4. LOT NO., RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Corner K12: Original monument and accessories not found.
 Corner J11: Original monument and accessories not found.
 Corner 9: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Corner K12: Restored 8-31-82 midway and on line between section corners north and south.
 Corner J11: Restored 8-31-82 midway and on line between section corners east and west.
 Corner 9: Established 9-3-82 during section subdivision

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner K12: Set 1" I.D. by 36" Iron Pipe w/4" alum. cap.
 12" J. Pine N49E 20.9 ft. 1/4S, NBT
 14" J. Pine N56W, 26.0 ft. 1/4S, NBT
 4" Maple S42W 27.0 ft. 1/4S, NBT
 Corner 9: Set 1" by 32" Iron Pipe w/4" alum. cap.
 6" Maple N14E 52.7 ft. 1/16S, BT
 6" Maple N88W, 25.6 ft. 1/16S, BT
 6" P. Pine S23E, 80.5 ft. 1/16S, BT
 Corner J11: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.
 10" J. Pine N38W 50.9 ft. 1/4S, NBT
 6" Maple S10E 56.6 ft. 1/4S, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2-26-83

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

