

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette

	Located In:	Corner Code
1. Public Land Survey	T <u>46N</u> R <u>27W</u>	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S <u>20</u> T _____ R _____	<u>11</u>
	S _____ T _____ R _____	<u>12</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on August 15, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

11	12
Not set in original survey nor subsequently, apparently.	Not set in original survey nor subsequently, apparently.
	Found 1" Drill Rod S58W 15.98 FT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11	12
Established during section subdivision.	Established during section subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

11	12
Set 1" I.D. x 36" iron pipe with 4" aluminum cap.	Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
8" oak N28E 8.2' 1/16s, BT	9" oak S78E 27.7' 1/16s, BT
9" sugar W50W 11.9' 1/16s, BT	6" maple N38E 26.8' 1/16s, BT
4" spruce S25E 9.5' 1/16s, BT	9" oak S70W 39.1' 1/16s, BT
7" balsam S27W 21.2' 1/16s, BT	Squared 9" v. birch South 2.0'



Signed by Keith Sackett

Date September 6, 1991

Surveyor's Michigan License No. 19006