

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**Marquette**

(County)	Located In:	Corner Code //
1. Public Land Survey	T <u>46N</u> R <u>27W</u>	<u>F10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>28</u> T _____ R _____	<u>8</u>
	S _____ T _____ R _____	<u>9</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Keith Sackett, in a field survey on August 15, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<b>F10</b>	<b>8</b>	<b>9</b>
Not set in original survey nor subsequently, apparently.	Not set in original survey nor subsequently, apparently.	Not set in original survey nor subsequently, apparently.
Found iron set by forester for approx. corner.	Found pipe set by forester for approx. corner.	Found pipe set by forester for approx. corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<b>F10</b>	<b>8</b>	<b>9</b>
Established at intersection of quarter lines.	Established midway and on line.	Established during section subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<b>F10</b>	<b>8</b>	<b>9</b>
Set 1" I.D. x 36" iron pipe with 4" aluminum cap.	Set 1" I.D. x 36" iron pipe with 4" aluminum cap.	Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
6" maple N36E 31.5' 1/4s, BT	18" oak N45E 40.0' 1/16s, BT	11" oak North 12.8' 1/16s, BT
7" v. pine S68W 18.3' 1/4s, BT	12" twin sugar east 55.5' 1/16s, BT	5" maple N43E 27.4' 1/16s, BT
5" maple N17W 20.8' 1/4s, BT	7" maple S04E 43.7' 1/16s, BT	5" v. pine S68W 47.1' 1/16s, BT
	4" squared maple N40W 2.0'	5" maple S01E 18.7' 1/16s, BT



Signed by Keith Sackett

Date September 6, 1991

Surveyor's Michigan License No. 19006