

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette
(County)

Located in: Corner Code #

1. Public Land Survey T 46H R 27W 010
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling S 29 T 46H R 27W 9
In Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

9 Oct 24 1996
D10 Oct 22 1996

I, Paul R. Bressette, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
(D10) Center Quarter corner of Section 29. Found 1/2 inch rebar, not of record.
(9) East One-sixteenth corner of Section 29. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(D10) Found 1/2 inch rebar with no cap 9.49 feet S29E (magnetic) of calculated position. No witnesses visible. Rejected rebar due to excessive distance from proper position and no record. Corner position established at the intersection of the north-south and east-west quarter lines of Section 29.
(9) Corner position established mid-point and on-line between the East and Center Quarter corners of Section 29. Corner falls in NE corner of a clearcut.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(D10) DNR monument
13" R.Pine N28E 113.65' (1/4S,BT)
05" Aspen S42E 16.4' (1/4S,BT)
06" R.Maple S49W 25.0' (1/4S,BT)
09" J.Pine N26W 69.5' (1/4S,BT)
All trees are blazed, scribed and painted. Measurements are to notch in butt blaze, bearings are magnetic.
(9) DNR monument
14" J.Pine N22E 20.25' (1/16S,BT)
05" J.Pine S69E 24.25' (1/16S,BT)
11" J.Pine S09E 44.2' (1/16S,BT)
10" J.Pine N60W 9.8' (1/16S,BT)
All trees are blazed, scribed and painted. Measurements are to notch in butt blaze, bearings are magnetic.



Signed by Paul R. Bressette
Surveyor's Michigan License No. 37270

Date 1-13-97

For the Michigan Department of Natural Resources - Forest Management Division