

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Marquette (County) Located In: Corner Code #
1. Public Land Survey T 46N R 27W 011
2. Property Controlling In Section S 29 T 46N R 27W 12
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

12 Oct 22 1996
011 Sep 18 1995

I, Paul R. Bressette, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column C and row 11.

A. Description of original monument and accessories and/or subsequent restoration:

(D11) Quarter corner common to Sections 29 and 32. GLO: Maple post witnessed by: Sugar 16 N66E 12 lks.; W.Pine 36 N17W 80 lks. 1967: Billy Buckler, RLS. Set DNR monument midway and on line between the Section corners witnessed by: 32" W.Pine N83E 46.8'; 10" W.Pine S17W 24.5'. 1983: David Erickson, RLS. Found DNR monument witnessed by: 32" W.Pine N86E 47.85' (NBT); 7" Balsam S55E 20.22'; 8" Balsam S01E 32.67'; 10" W.Pine S19W 24.68' (NBT); 6" Maple S63W 39.20'. Distances to 6" spike in side of tree. (12) South One-sixteenth corner of Section 29. Found iron bolt with 3" aluminum collar and 2 apparent witnesses. Not of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D11) Found monument as described, NBT's have all been destroyed by ELF construction and logging activities. Monument was rewitnessed as found and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner. (12) Found iron bolt 48.6 feet southerly of calculated position. Rejected bolt due to excessive distance from proper position and no record. Corner position established mid-point and on-line between the South and Center Quarter corners of Section 29.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D11) DNR monument (12) DNR monument
6" W. Birch S06E 39.1' (1/4S, NBT) 7" W. Pine N36E 123.0' (1/16S, BT)
6" R. Maple S26W 50.5' (1/4S, NBT) 8" W. Pine S31E 40.55' (1/16S, BT)
7" R. Maple S81W 33.5' (1/4S, NBT) 4" W. Pine S79W 5.0' (1/16S, BT)
6" W. Spruce N87W 67.4' (1/4S, NBT) 7" W. Pine N14W 59.05' (1/16S, BT)
All trees are blazed, scribed and painted. Measurements are to notch in butt blaze, bearings are magnetic. A metal post with sign was placed next to monument.



Signed by Paul R. Bressette
Surveyor's Michigan License No. 37270

Date 1-13-97

For the Michigan Department of Natural Resources - Forest Management Division