

1994 DEC 28 PM 5:57

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 94030  
SHEET NO.: 1-493  
Corners in

*Patricia A. Morley*  
REGISTER OF DEEDS

MARQUETTE  
(County)

Located In:

Corner Code #

Public Land Survey

T 47N R 27W  
T 46N R 27W

G-13:

G-1 ✓

Property Controlling

in Section

Miscellaneous

Property in Sec.

S T R  
S T R  
S T R  
S T R

LIBER

1 PAGE 163

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

GERALD W. CARLSON, in a field survey on Monday, December 19, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as crossed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

G-13: Section Corner common to Section 3 & 4, T46N-R27W and 10" Spruce S48E 57 1  
 Sections 33 & 34, T47N-R27W. 12" Sugar S35W 32 1

1846: Austin Burt's original survey notes describe the corner monument as a sugar post referenced by:  
 6" Sugar N65E 45 1  
 6" Fir N78 1/2W 30 1

1848: Harvey Mullen's original subdivision survey notes for T46N-R27W indicated the following additional references for the NW Corner of Section 3, T46N-R27W:  
 1921: Old CCI field notes indicate a "I.P." on a Section sheet at the SW Corner of Section 34, T47N-R27W.  
 1978: Survey recorded in Liber 330, pg. 805 by Charles P. Clark RLS No. 25836 indicates a 3/4" iron pin at the NW corner of Section 3, T46N-R27W. No corner accessories given. (See reverse side)

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted 3/4" iron pin as referenced in part "A" above.  
Distance West is 2609.45' and distance East is 2616.65'.

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

*Larry J. Bessant*  
DATE Nov 21, 1994

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Replaced 3/4" iron with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

5" Triple Maple N06E 17.75 ft. Clark NBT  
 6" Balsam S82E 3.65 ft. Clark NBT  
 10" White Birch S22W 3.67 ft. Clark NBT  
 4" Balsam N50W 9.76 ft.

Steel sign post East 1.0 ft.  
 Monument is 0.20' above ground.  
 Bk. 8, Pg. 49

by *Gerald W. Carlson*  
Surveyor's Michigan License No. 24589

Date 12-22-94



Record No. 493

1978: Land Corner Recordation Certificate filed by Charles F. Clark RLS No. 25836 indicates a found 3/4" iron pin witnessed by nails in:

3"	Spruce East	3.53'
12"	Birch S18W	3.69'
3"	Maple N07E	17.77'

Liber, 1RC pg. 239

1986: Certificate of Survey recorded Liber, 358 Pg. 631 filed by James Minard RLS No. 30091 indicated the NW corner of Section 3, T46N-R27W as a found 3/4" pin (L, 1RC, pg. 239).

*Ret. to  
Liber  
pg. 631*