

JUL 03 2000

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:57

JOB NUMBER: 94030

SECTION

SHEET NO. : 1-197

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>47N</u> R <u>27W</u>	K-13
	T <u>46N</u> R <u>27W</u>	K-1 ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Patricia A. Monlay
REGISTER OF DEEDS

LIBER **R1** PAGE **167**
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Tuesday, December 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13: Section Corner common to Sections 1 & 2, T46N-R27W 12" Sugar S81W 31 l
and Sections 35 & 36, T47N-R27W. 9" Fir S15E 35 l

1846: Austin Burt's original survey notes describe the corner monument as a Cedar post referenced by:
8" Fir N41E 23 l
16" Sugar N48W 30 l

1848: Harvey Mullen's original subdivision notes for T46N-R27W indicate the following additional references for the NE Corner of Section 2, T46N-R27W:
No date given: Old field notes from C.C.I. Section 35, T47N-R27W, indicates the SE Corner of Section 35 as a B.T. Corner. No corner accessories given.
1963: Land Corner Record filed by R.J. Brotherton indicates an old Cedar post set new post at 3/4" iron drill rod referenced by: (See reverse side).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Corner position established by a line Due West (Solar) 2656.60' from an iron set by R. J. Brotherton in 1976 for the South 1/4 Corner of Section 36. Distance West is 2665.16' and distance East is 2637.37'. This corner position lands in the Tilden Mine re-use pond. A CCI Company drill rod in rock is used as a witness to the Section Corner. The bearing from the drill rod to the rock is N78°19'00"E, 308.72'. An additional witness monument (Marquette County Survey Monument) was set S01°58'15"W, 199.00' from the drill rod. The extension of the line from the Witness Monument to the drill rod extended N01°58'15"E, 70.97' intersects the South line of Section 35, N88°23'36"W, 300.00' from the Section Corner. (See back for sketch)

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE Dec 6, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

4" Oak N61E 21.87 ft.
7" Maple S70E 25.97 ft.
9" Spruce S34E 47.93 ft.
5" Maple S13E 17.39 ft.
Steel sign post South 1.0 ft.

Monument is 0.40' above ground. Corner is 24' South of centerline of two track mine road.
Bk. 8, Pg. 61



Signed by Gerald W. Carlson Date 12-22-94
Surveyor's Michigan License No. 24589

Record No. 497

*R. Oak
S. Maple
2000 B.M.*

12"	R. Oak	N63W 5.8'	Notched reference trees
8"	S. Maple	S13W 12.6'	Notched reference trees

Old stake and a Maple stub B.T. marks on it were here in December 28, 1938 in cruise report of RJB. RAB reports the same in 1908. The iron drill rod was set in old stake hole by RJB 3-61. B.T. is now decayed away.

