

1994 DEC 28 PM 5:57

Patricia A. Manley
REGISTER OF DEEDS *PM*

LIBER **1** PAGE **168**
Register of Deeds Stamp & File Number

JOB NUMBER: 94030

SHEET NO. : 1-498

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Four corners in

MARQUETTE
(County)

Located in:

Corner Code #

Public Land Survey

T 47N R 27W
T 46N R 27W

L-13

L-1

Property Controlling
in Section

S T R

Miscellaneous

S T R

Property in Sec.

S T R

Lot No. _____, Recorded Plat _____

Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

GERALD W. CARLSON : in a field survey on Monday, December 19, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as witnessed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- L-13: 1/4 Corner common to Sections 1, T46N-R27W and Section 36, T47N-R27W. 3" Spruce S83W 16.2' 12" Pine S18W 10.2'
- 1846: Austin Burt's original survey notes describe the corner monument as a Cedar post referenced by: 10" White Birch N07W 21 1 7" Fir N84W 72 1 1932: M.C.R.C. field book 570 indicates the North 1/4 Corner of Section 1, T46N-R27W is a 10" squared Birch stump referenced by:
- 1976: Land Corner Record from C.C.I. Forest Products Division indicates the corner is a 1" drill rod referenced by: 6" Sugar Maple AZ.120 10.0' 4" Maple S89E 6.57' old bearing 13" Fir S34W 8.78' old bearing Tag 10" White Birch 106.5' West, 9.0' North of South 1/4 Corner 248 degrees - 96.0' to pole. (See reverse side).

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Corner position established equidistant and on line between the Southwest and Southeast Corners of Section 36. Distances West and East are 2637.37'. The previous position established by Brotherton was considered incorrect as the Southeast Corner of Section 36 was not considered in his survey. The re-established Southeast Corner of Section 36 (BCI double proportion - 1978) was re-calculated using the re-established Southwest Corner of Section 36 and the position would move very little. It was decided by the Marquette County Peer Group to leave the re-established Southeast Corner of Section 36 in place and re-establish the South 1/4 Corner of Section 36 as, stated above. The re-established South 1/4 Corner is S29-10'23"W, 40.77' from the Brotherton iron.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bueane
DATE Dec 6, 1994

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey monument stamped to identify the corner referenced by nails in:
 - Twin Jack Pine S10E 35.75 ft.
 - Jack Pine S35W 19.98 ft.
 - White Pine N47W 4.57 ft.
 - White Pine N39E 9.30 ft.
 - Steel sign post East 1.0 ft.
- Monument is 0.30' above ground. Monument is 51.5' East of two track road.
- . 8, Pg. 47



by Gerald W. Carlson Date 12-22-94

Surveyor's Michigan License No. 24589

Record No. 498

Corner was set by running transit line due East from bearing tree corner at NW Section Corner.

1/4 Corner is 2656.60' East of the Section Corner .

1978: Land Corner Recordation Certificate filed by Charles F. Clark RLS No. 25836 found a 1" drill rod in stone pile and C.C.I.C. location tag referenced by:

Spike in P. pole	S71 56" West 96.62'
Spike in P. pole	N0 34" West 181.48'
Spike in 5" Maple stump	N85E 6.78'

Liber, 1RC, pg. 233

*Ret 6/4
Geo
Joel Bern*