

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MARQUETTE COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 28 W.	C 8
2. PROPERTY CONTROLLING IN SECTION	19 T. 46 N. R. 28 W.	7, 14
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-2- 19 83, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner C 8: Original monument and accessories not found.
- Corner 7: Not set on original survey. Found an iron pipe with cap west 53.4 ft., origin unknown.
- Corner 14: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner C 8: Restored midway and on line between section corners north and south.
- Corner 7: Established midway and on line between section corner north and 1/4 corner south.
- Corner 14: Established midway and on line between section corner south and 1/4 corner north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Corner C 8: Set 1: I.D. by 32" iron pipe w/4" alum. cap.
4" Spruce N59E 17.6 ft. 1/4S, NBT
3" Spruce S34E 24.2 ft. 1/4S, NBT
7" Spruce S85W 18.1 ft. 1/4S, NBT
4" Balsam squared N39W 1.2 ft. marked 19 & 20.
Corner 7: Set 1" I.D. by 32" iron pipe w/4" alum. cap.
6" J. pine west 61.4 ft. 1/16S, BT
7" Balsam S57W 58.2 ft. 1/16S, BT | Corner 14: Set 1" I.D. by 32" Iron pipe w/4" alum. cap.
26" R. pine S60E 36.4 ft. 1/16S, BT
10" R. pine N49W 22.8 ft. 1/16S, BT
9" Spruce S52W 28.0 ft. 1/16S, BT |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-4-83
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

