

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY...	T. 46 N. S. R. 28 E. W.	K7, L7, K8
2. PROPERTY CONTROLLING IN SECTION 24	T. 46 N. S. R. 28 E. W.	10
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-8- 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Corner K7: Original monument and accessories not found.
 Corner L7: Original monument and accessories not found.
 Corner K8: Original monument and accessories not found.
 Corner 10: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Corner K7: Restored by double proportion distance from corners north- south-east-west. Location fits good with land calls.
 Corner L7: Restored on line midway between corners east and west.
 Corner K8: Restored on line midway between corners north and south.
 Corner 10: Established midway and on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner K7: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.
 12" J. pine S81E 11.2 ft. S24, NBT
 12" J. pine S71W 13.7 ft S23, NBT
 12" Spruce N25E 28.8 ft. S13, NBT
 Corner K8: Set 1" I.D. by 32" iron pipe w/4" alum. cap.
 8" J. pine S60W 14.8 ft. 1/4S, NBT
 12" J. pine S31E 8.0 ft. 1/4S, NBT
 6" J. pine N16W 28.3 ft. 1/4S, NBT
 Corner L7: Set 1" I.D. by 32" iron pipe w/4" alum. cap.
 10" J. pine N41E 9.6 ft. 1/4S, NBT
 9" J. pine S28E 15.1 ft. 1/4S, NBT
 9" J. pine N89W 24.3 ft. 1/4S, NBT
 Corner 10: Set 1" I.P. by 32" iron pipe w 4" alum. cap
 9" J. pine S34W 14.5 ft 1/16S, BT
 8" J. pine N33W 14.7 ft. 1/16S, BT
 10" J. pine S65E 11.7 ft. 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett
 CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

