

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 27-28W


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19-20-24-25

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/29/64

WITNESSES TO CORNER..... 13" Jackpine (S25 NBT) S78°W 11 Lts.



12" Jackpine (S19 NBT) N41°E 22 Lts.

11" Jackpine (S20 NBT) S70°E 14 Lts.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Single Proportionate Measure along Township Line. Found and old blazed Jackpine 29 Mils South of Corner. Placed Location Poster 3/4 chain West on Road.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED BILLY D. BUCKLER DATE 8/4/1964
REGISTERED LAND SURVEYOR