

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 27-28N


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to sections 30-31-25-36

CORNER MONUMENT 1" Pine with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/29/64

WITNESSES TO CORNER..... 8" Jackpine (S31 EBT) S32°E 07 lts.



8" Jackpine (S25 EBT) N30°W 26 1/2 lts.

9" Jackpine (S36 EBT) S70°W 37 1/2 lts.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Single Proportionate Measure along Township Line. Found no Original evidence. Placed Location Poster 5 1/2 Chains West on old Woods Road.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED BILLY D. BUCKLER DATE 8/4/1964
REGISTERED LAND SURVEYOR