

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 27-28


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 7-18-12-13

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 6/15/64 with Arthur Klawiter

WITNESSES TO CORNER..... 10" Jack Pine (S7 MBT) N70° E 26 lts.



CIRCLE CORNER REGISTERED

9" Jack Pine (S13 MBT) S 15° W 06 lts.

4" Jack Pine (S12 MBT) S51° W 23 lts.

AND

Corner lies 1 3/4 chains North of Trailroad

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced at a squared Jackpine tree. This tree blazed about 14 years ago by unknown persons. Distance checks well to Corner 1 mile East, Swamp edges East, West and South. No evidence of Original Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler.
BILLY D. BUCKLER
REGISTERED LAND SURVEYOR

DATE 7/29/1964