

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46N N.R. 28W


Marquette COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to 9-10-15-16

CORNER MONUMENT 1" Pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 4/27/67

WITNESSES TO CORNER..... 14" Jack pine (S10 NBT) N20°E 36.0'



19" White pine (S9 NBT) N30°W 57.2'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established from sec. cor. 1 mile north, river bank to south and east and swamp edge to west. Found no evidence of original corner.

Corner set with Paul Hannuksela, Marquette.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE May 27, 1967
REGISTERED LAND SURVEYOR