

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | | |
|----------|---------------------------------------------|---------------|----------------|
| T | Marquette <small>(County)</small> | Located In: | Corner Code // |
| 1 | Public Land Survey | T 46N R 28W | D5 |
| | | T R | D7 |
| | | T R | E6 |
| | | T R | |
| 2 | Property Controlling in Section | S 17 T R | 14 |
| | | S T R | |
| 3 | Miscellaneous Property in Sec | S T R | |
| | | S T R | |
| 4 | Lot No | Recorded Plat | |
| 5 | Private Claims | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 |
| 3 | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 |
| 7 | | | | | | | | | | | | | |
| 8 | 27 | 28 | 29 | 30 | 31 | 32 | 33 | 34 | 35 | 36 | 37 | 38 | 39 |
| 9 | | | | | | | | | | | | | |
| 10 | 42 | 43 | 44 | 45 | 46 | 47 | 48 | 49 | 50 | 51 | 52 | 53 | 54 |
| 11 | | | | | | | | | | | | | |
| 12 | 59 | 60 | 61 | 62 | 63 | 64 | 65 | 66 | 67 | 68 | 69 | 70 | 71 |
| 13 | | | | | | | | | | | | | |

I, **Keith Sackett**, in a field survey on **January 31**, 19**91**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

| | | | |
|----------------------------------------------|----------------------------------------------|----------------------------------------------|----------------------------------------------------------|
| D5 | D7 | E6 | 14 |
| Original monument and accessories not found. | Original monument and accessories not found. | Original monument and accessories not found. | Not set on original survey nor subsequently, apparently. |

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

| | | | |
|------------------------------|------------------------------|------------------------------|---------------------------------|
| D5 | D7 | E6 | 14 |
| Restored midway and on line. | Restored midway and on line. | Restored midway and on line. | Established midway and on line. |

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|
| D5 | D7 | E6 | 14 |
| Set 1" ID x 36" iron pipe with 4" aluminum cap. 6" spruce S60E 24.9' 1/4s NBT 4" v. pine N35W 39.3' 1/4s NBT 7" j. pine S74W 37.4' 1/4s NBT 8" j. pine N27W 5.4' squared | Set 3-7-91 1" ID x 36" iron pipe with plastic cap. 4" tamarack N80E 35.1' 1/4s NBT 3" tamarack S18W 48.5' 1/4s NBT 4" tamarack S18W .8 squared 3" tamarack N04E 19.8' 1/4s NBT | Set 3-5-91 1" ID x 32" iron pipe with 4" aluminum cap. 3" spruce S47E 18.7' 1/4s NBT 2" spruce N37E 11.3' 1/4s NBT 4" tamarack N63W 32.9' 1/4s NBT | Set 1" ID by 36" iron pipe with 4" aluminum cap. 3" spruce N7W 4.6' 1/16s BT 4" spruce N81E 19.4' 1/16s BT 3" spruce S11W 18.0' 1/16s BT |

Signed by

Keith Sackett

Date

STATE OF MICHIGAN
 1991
 March 14, 1991

Surveyor's Michigan License No.

19006