

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

T	Marquette (County)	Located In	Corner Code //
1	Public Land Survey	T 46N R 24W	D6
		T R	
		T R	
		T R	
2	Property Controlling in Section	S 17 T R	5
		S T R	8
3	Miscellaneous Property in Sec	S T R	12
		S T R	
4	Lot No	Recorded Plat	
5	Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	14	15	16	17	18							
7													
8	19	20	21	22	23	24							
9													
10	25	26	27	28	29	30							
11													
12	31	32	33	34	35	36							
13													

I, **Keith Sackett**, in a field survey on **March 7**, 19**91**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration

D6	5	8	12
Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner.

D6	5	8	12
Established at intersection 1/4 lines.	Established during subdivision.	Established during section subdivision.	Established during subdivision.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner.

D6	5	8	12
Set 3-7-91 1" ID x 32" iron pipe with 4" aluminum cap. 3" spruce N67E 182' 1/4s BT 8" j. pine S40W 71.0' 1/4s BT 3" spruce N30W 27.3' 1/4s BT	set 3-7-91 1" ID x 36" iron pipe with 4" aluminum cap. 12" j. pine S82E 5.2' 1/16s BT 10" j. pine S06W 32.0' 1/16s BT 8" j. pine N33W 9.9' 1/16s BT	Set 3-7-91 1" ID x 36" iron pipe with 4" aluminum cap. 7" j. pine S31E 18.0' 1/16s BT 6" j. pine S38W 24.8' 1/16s BT 7" j. pine N55W 24.7' 1/16s BT	Set 3-7-91 1" ID x 36" iron pipe with 4" aluminum cap. 7" spruce N38E 9.1' 1/16s BT 7" spruce S06E 12.8' 1/16s BT 6" spruce S76W 10.1' 1/16s BT 3" spruce N40W 1.5' squared

Signed by

Keith Sackett

Date

March 14, 1991

Surveyor's Michigan License No

19006