

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<b>T</b>	<b>Marquette</b> <small>(County)</small>	Located In	Corner Code //
1	Public Land Survey	T 46N R 20W	E7
		T R	
		T R	
		T R	
2	Property Controlling in Section	S 17 T R	7
		S T R	
3	Miscellaneous Property in Sec	S T R	
		S T R	
4	Lot No	Recorded Plat	
5	Private Claims		

Register of Deeds Stamp & File Number

I, **Keith Sackett**, in a field survey on **March 5**, 19**91**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E7	7
Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.
1 1/4" ID x unknown length iron pipe.	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

E7	7
Restored at iron pipe. Local resident George Swanson says pipe has been in place for 55 years.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E7	7
Restored at found iron pipe	Set 1" ID x 32" iron pipe with
5" balsam S35E 4.6' S21 NBT	4" aluminum cap
4" balsam S86W 12.7' S20 NBT	14" j. pine N39E 8.4' 1/16s BT
3" balsam N10W 14.6' S17 NBT	10" j. pine S32E 17.9' 1/16s BT
	12" j. pine S26W 19.9' 1/16s BT

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	14	15	16	17	18							
7													
8	19	20	21	22	23	24							
9													
10	25	26	27	28	29	30							
11													
12	31	32	33	34	35	36							
13													

Signed by *Keith Sackett*  
 Surveyor's Michigan License No 19006

Date

March 15, 1991

