

# LAND CORNER RECORDATION CERTIFICATE

ARQUETTE COUNTY

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. S. R. 28 K. W.	C3, B3, C7
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner C3: Original monument and accessories not found.
  - Corner B3: Original monument and accessories not found. Found knob of granite 15 ft. high 1.50 chains west of corner as per original notes.
  - Corner C7: Original monument and accessories not found.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner C3: Restored 10-5-83 by double proportion between corners and land calls.
  - Corner B3: Restored 10-5-83 from land calls west and section corner east. It also fits reasonable with section corner west.
  - Corner 7: Restored 10-24-83 by double proportion. Fits good with land calls.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner C3: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.  
10" maple S83W 20.6 ft. S7, NBT  
6" maple S74E 13.1 ft. S8, NBT  
4" maple N38E 13.8 ft. S5, NBT
  - Corner C7: Set 1" I.D. by 32" I.P. w/4" alum. cap.  
14" w. pine N40E, 35.6 ft. S17, NBT  
11" balsam S72W 23.5 ft. S19, NBT  
9" w. pine S28E, 30.0 ft. S20, NBT
  - Corner B3: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.  
7" maple S54E 17.7 ft 1/4S, NBT  
12" maple N62E 32.1 ft 1/4S, NBT  
24" spruce N74W 41.4 ft. 1/4S, NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 11-12-83

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

