

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE COUNTY

FOR CORNERS OF --:	LOCATED IN --:			CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T 46	N. X. R. 28	E. W.	E5, F5
2. PROPERTY CONTROLLING IN SECTION 9	T 46	N. X. R. 28	E. W.	16
3. MISCELLANEOUS PROPERTY IN SECTION	T	N. S. R.	E. W.	-----
4. LOT NO. RECORDED PLAT				-----
5. PRIVATE CLAIMS				-----

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-28, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law.

A. Description of original monument and accessories and or subsequent restoration:

Corner E5: Original monument and accessories not found. Found 1" drill steel at location that fits land calls to north - east - west.

Corner F5: Original monument and accessories not found.

Corner 16: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and or method applied in restoring or re-establishing corner:

Corner E5: Restored corner at 1" drill steel.

Corner F5: Restored corner on line and midway between section corners east and west.

Corner 16: Established on line and midway between 1/4 corner west and section corner east.

C. Description of monument to, corner and accessories established to perpetuate locating the position of the corner:

Corner E5: 1" drill steel.	Corner 16: Set 1" I.D. by 32" Iron pipe.
8" J. pine N10E 24.3 ft. S9, NBT	5" Sugar N70W 14.5 ft, 1/16S, BT
9" J. Pine S46E 20.7 ft. S16, NBT	8" Maple N35E 6.0 ft. 1/16S, BT
6" W. birch S45W 31.0 ft. S17, NBT	4" W. Pine S34E 19.3 ft. 1/16S, BT

Corner F5: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.  
No available witnesses. Corner falls on north bank of Black River.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 7-16-83  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006