

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Marquette (County) Located In: Corner Code #
1. Public Land Survey T R
2. Property Controlling in Section S 27 T 46N R 28W 8
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Sep 22 1997

I, Paul R. Bressette, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numerical data and two dots in the grid.

- A. Description of original monument and accessories and/or subsequent restoration:
8) West One-sixteenth corner of Section 27. Not set in original survey, no evidence of subsequent establishment.
14) South One-sixteenth corner common to Sections 26 and 27. Not set in original survey, no evidence of subsequent establishment.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
8) Corner position establishment mid-point and on-line between the West and Center Quarter corners of Section 27.
14) Corner position established mid-point and on-line between the Southeast and East Quarter corners of Section 27.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
8) DNR monument (14) DNR monument
4" J.Pine N30E 74.15' (1/16S,BT) 13" J.Pine S64E 24.95' (1/16S,BT)
4" J.Pine S87E 58.4' (1/16S,BT) 15" J.Pine S16E 29.1' (1/16S,BT)
0" J.Pine S54W 32.15' (1/16S,BT) 13" J.Pine S65W 23.6' (1/16S,BT)
2" J.Pine N26W 80.5' (1/16S,BT) 06" J.Pine N73W 13.3' (1/16S,BT)
11 trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.
All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette Date
Surveyor's Michigan License No. 37270

For the Michigan Department of Natural Resources - Forest Management Division