

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette
(County)

Located in:

Corner Code #

1. Public Land Survey

T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling
in Section

S 27 T 46N R 28W 5
S 27 T 46N R 28W 6

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___
S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

6 Oct 16 1997
5 Oct 14 1997

I, Paul R. Bressette, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 5) Witness corner 50 feet east of the North 1/16 corner of Section 27. Corner position falls in approximate centerline of stream.
- 6) Northeast One-sixteenth corner of Section 27. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 5) True corner position established mid-point and on-line between the North and Center Quarter corners of Section 27. Witness corner laced 50 feet east and on the north one-sixteenth line of Section 27.
- 6) Corner position established at the intersection of the North and East One-sixteenth lines of Section 27.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-------------------------------|----------------------------------|
| 5) DNR monument | (6) DNR monument |
| 8" J.Pine N50E 16.35' (WC,BT) | 10" J.Pine S31E 57.8' (1/16S,BT) |
| 5" J.Pine N82E 16.35' (WC,BT) | 09" J.Pine S34W 30.8' (1/16S,BT) |
| 0" J.Pine S28E 6.2' (WC,BT) | 05" J.Pine S51W 21.7' (1/16S,BT) |
| 4" J.Pine S34W 8.1' (WC,BT) | 07" J.Pine N86W 47.3' (1/16S,BT) |
- 11 trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division