

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette
(County)

Located In: Corner Code -##

- 1. Public Land Survey T 46N R 28W M7
T 46N R 28W M8
T R
T R
2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and two black dots in the 7th and 8th rows.

M8 January 05, 1995

I, Paul R. Bressette, in a field survey on M7 January 12, 1995, 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M7) Section corner common to Sections 13, 24, 18 and 19. 1964: Billy Buckler, RLS 08887. Set 1" iron pipe with 4" brass cap witnessed by: 11" J. Pine S67E 41.5 lks.; 11" J. Pine N27W 188 lks.
(M8) Quarter corner common to Sections 24 and 19. 1986: Keith Sackett, RLS 19006. Set DNR monument witnessed by: 12" J. Pine S74E 37.7'; 12" J. Pine S89W 9.4'; 10" J. Pine N36W 23.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument as described, the NW NBT dead but standing, and a stump in position for SE NBT. Accepted monument as found and re-witnessed. Corner is south of a trail road in the southeast corner of a clearcut. The gate post is 8" x 6" oak.
(M8) Found monument as described, the SW NBT is a blow down, and the remaining NBT's have been cut. Accepted monument as found and re-witnessed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M7) 1" iron pipe w/ brass cap
7" J. Pine N41E 50.55'
8" J. Pine S32E 15.05'
8" J. Pine S20W 19.9'
N'yly gate post N50 W 19.9'
All trees are face and butt blazed, scribed with section number and NBT. Measurements are to notch in butt blaze, except gate post which has PK nail w/ DNR reference tag. Bearings are magnetic.
(M8) DNR monument
6" J. Pine N32E 31.45'
7" J. Pine S81E 28.75'
7" J. Pine S09E 38.75'
6" J. Pine S70W 5.55'
All trees are face and butt blazed, scribed 1/4S, NBT. Measurements are to notch in butt blaze. Bearings are magnetic.



Signed by Paul R. Bressette Date

Surveyor's Michigan License No. 37270