

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE COUNTY		CORNER CODE NUMBER
FOR CORNERS OF--	LOCATED IN--	
1. PUBLIC LAND SURVEY	T. 46 N. X , R. 29 X W.	K-4
2. PROPERTY CONTROLLING IN SECTION 11	T. 46 N. X , R. 29 X W.	7 & 14
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S., R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner K4 (1/4 corner between Sections 11 & 12, T46N, R29W):
 Yellow Birch post (Not found. No subsequent monuments found.)
 Spruce 18 N54E 34 (Not found. No subsequent accessories found.)
 Fir 12 S69W 14 (Not found. No subsequent accessories found.)

Corner 7 (North 1/16 corner between Sections 11 & 12, T46N, R29W) and
Corner 14 (South 1/16 corner between Sections 11 & 12, T46N, R29W):
 Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner K4: Restored 7/10/78 on line between original section corners 39.964 ch. to N and to S. Position falls at base of a large, embedded boulder or rock outcrop.
Corner 7: Established 8/29/78 on line between 1/4 cor. 19.982 ch. S and Sec. Cor. 19.982 ch. N.
Corner 14: Established 8/1/78 on line between Sec. Cor. 19.9825 ch. S and 1/4 cor. 19.9825 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Monuments for all 3 corners: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Witnesses for Corner K4: W. Birch 11 S76°W (mag.) 7.7 ft. "1/4S, NBT"
 Declination 0°20' West. R. Maple 8 S83°E (mag.) 20.1 ft. "1/4S, NBT"
 ⊕ Chiselled in boulder S89°E (mag.) 5.40 ft.
Note: This mon. set at angle to N, on account of an unexcavatable boulder below ground. Punch mark in mon. is over true point.
Witnesses for Corner 7: W. Pine 29 S 6°W (mag.) 19.3 ft. "1/16S, BT"
 Declination 1°50' West. W. Pine 17 N63°W (mag.) 16.7 ft. "1/16S, BT"
 Monument set in mound of rocks.
Witnesses for Corner 14: B. Spruce 6 N72°E (mag.) 6.2 ft. "1/16S, BT"
 Declination 1°30' West. B. Spruce 5 N25°W (mag.) 8.0 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (BEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE Mar 2 1978
 CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

