

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	<u>MARQUETTE COUNTY</u> LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. <u>46</u> N. <u>X.</u> R. <u>29</u> X. W.	J-4	
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	T. <u>46</u> N. <u>X.</u> R. <u>29</u> X. W.	9 & 9a	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. S. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND
FILING NUMBER _____

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 28, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner J4 (Center of Section 11, T46N, R29W) and

Corner 9 (East 1/16 corner on E & W 1/4 line of Section 11, T46N, R29W) and

Corner 9a (West Aux. M.C. on E & W 1/4 line of Section 11, T46N, R29W):
None of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner J4: Established at intersection of quarter-section lines.

Corner 9: Established on E & W 1/4 line 20.060 ch. W of E 1/4 cor. and 20.060 ch. E of Center 1/4 cor.

Corner 9a: Established on E & W 1/4 line on west shore of Birch Lake, 4.886 ch. E of Center 1/4 cor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all 3 corners: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

Witnesses for Corner J4: White Pine 12 N17°W (mag.) 27.6 ft. "1/4S, BT"
Declination 1°30' West. Red Maple 10 S74°W (mag.) 27.1 ft. "1/4S, BT"

Witnesses for Corner 9: White Pine 6 S11°W (mag.) 20.4 ft. "1/16S, BT"
Declination 1°55' West. Red Maple 7 N86°W (mag.) 12.3 ft. "1/16S, BT"
Distances horizontal.

Witnesses for Corner 9a: B. Spruce 6 S31°E (mag.) 28.7 ft. "AMC, BT"
Declination 1°30' West. W. Pine 15 S15°W (mag.) 15.2 ft. "AMC, BT"
Distances horizontal.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE March 15, 1979

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

