

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	<u>MARQUETTE COUNTY</u> LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLLING IN SECTION <u>11</u> , T. <u>46</u> N. S., R. <u>29</u> <input checked="" type="checkbox"/> W.		5, 5a, & 5b
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 28, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 5 (North 1/16 corner on N & S 1/4 line of Section 11, T46N, R29W) and
 Corner 5a (North Aux. M.C. on N & S 1/4 line of Section 11, T46N, R29W) and
 Corner 5b (South Aux. M.C. on N & S 1/4 line of Section 11, T46N, R29W):
 None of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 5: Established on N & S 1/4 line 20.129 ch. S of N 1/4 cor. and 20.129 ch. N of Center 1/4 cor.
 Corner 5a: Established on N & S 1/4 line on north shore of Birch Lake, 5.825 ch. S of N 1/16 cor. on N & S 1/4 line and 14.304 ch. N of Center 1/4 cor.
 Corner 5b: Established on N & S 1/4 line on south shore of Birch Lake, 2.918 ch. N of Center 1/4 cor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all 3 corners: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Witnesses for Corner 5: W. Pine 22 N19°W (mag.) 14.5 ft. "1/16S, BT"
 Declination 1°55' West. W. Pine 22 S33°W (mag.) 9.5 ft. "1/16S, BT"
 Witnesses for Corner 5a: R. Pine 6 S43°W (mag.) 30.2 ft. "AMC, BT"
 Declination 1°50' West. R. Pine 6 N63°E (mag.) 15.0 ft. "AMC, BT"
 Witnesses for Corner 5b: W. Pine 14 N42°W (mag.) 17.9 ft. "AMC, BT"
 Declination 1°55' West. W. Pine 7 S45°W (mag.) 18.7 ft. "AMC, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 15, 1979
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

