

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF -: | MARQUETTE COUNTY LOCATED IN -: | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____ T. 46 N. 29 <input checked="" type="checkbox"/> W. | X. R. 29 <input checked="" type="checkbox"/> W. | J-5 |
| 2. PROPERTY CONTROLLING IN SECTION 11 _____ T. 46 N. 29 <input checked="" type="checkbox"/> W. | X. R. 29 <input checked="" type="checkbox"/> W. | 12 & 16 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S. R. _____ E. W. | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner J5 (1/4 corner between Sections 11 & 14, T46N, R29W):

- Tamarack post (Not found. No subsequent monuments found.)
- Spruce 10 S69W 3 (Not found. No subsequent accessories found.)
- Spruce 5 N64E 9 (Not found. No subsequent accessories found.)

Corner 12 (South 1/16 corner on N & S 1/4 line of Section 11, T46N, R29W) and

Corner 16 (East 1/16 corner between Sections 11 & 14, T46N, R29W):

Neither of these corners established in original survey and by approximation only, subsequently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner J5:** Restored 8/1/78 on line between Sec. Corners 40.132 ch. to E and to W.
- Corner 12:** Established 9/6/78 on line between S 1/4 cor. 19.991 ch. S and Center 1/4 cor. 19.991 ch. N. Found a 2" x 2" x 3' squared hdwd. post S7°E 33.6 ft. for an approx. corner.
- Corner 16:** Established 8/1/78 on line between Sec. Cor. 20.066 ch. E and 1/4 cor. 20.066 ch. W. Found an axle shaft placed in ground S18°E 12.1 ft., set at site of a chainage marker for an incomplete 1966 survey. The chainage marker was intended only to mark a point on a random transit line, not the true corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Monuments for all 3 corners:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
- Witnesses for Corner J5:** Tamarack 8 S14°E (mag.) 26.0 ft. "1/4S, NBT"
- Declination 2°00' West.** Tamarack 6 N10°W (mag.) 20.4 ft. "1/4S, NBT"
- Witnesses for Corner 12:** Red Maple 11 N21°E (mag.) 27.2 ft. "1/16S, BT"
- Declination 1°15' West.** Red Maple 6 N16°W (mag.) 6.9 ft. "1/16S, BT"
- Witnesses for Corner 16:** B. Spruce 6 N 9°E (mag.) 11.0 ft. "1/16S, BT"
- Declination 1°30' West.** B. Spruce 6 S61°E (mag.) 10.7 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE March 15, 1979
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

