

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	MARQUETTE COUNTY LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 46 N. X R. 29 X W.	I-5
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	T. 46 N. X R. 29 X W.	10 & 15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 15 (Section Corner 10,11,14, & 15, T46N, R29W):**
 Wood post (Not found. See B for approx. cor. monument.)
 Spruce 14 S45E 2 (Not found. No subsequent accessories found.)
 Maple 12 N 2W 34 (Not found. No subsequent accessories found.)

Corner 10 (South 1/16 corner between Sections 10 & 11, T46N, R29W) and

Corner 15 (West 1/16 corner between Sections 11 & 14, T46N, R29W):

Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 15:** Restored 7/10/78 5.25 ch. (the record distance) S of a probable original W. Pine 42 line tree stump, identified by position in relation to a post at the NW cor. of Sec. 11, swamp edges, and a distinctive small knob noted in the original field notes. Corner placed on S'yly extension of line bet. Sec. Cor. to N and L.T. stump. Fits with swamp E. Found a recent 2" x 2" x 5' squared post S71°E 29.5 ft. for an approx. corner.
- Corner 10:** Established 9/6/78 on line between Sec. Cor. 20.000 ch. S and 1/4 cor. 20.000 ch. N. **Corner 15:** Established 9/6/78 on line between Sec. Cor. 20.066 ch. W and 1/4 cor. 20.066 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Monuments for all 3 corners:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
- Witnesses for Corner 15:** J. Pine 11 N31°E (mag.) 45.1 ft. "S11, NBT"
 W. Pine 10 S64°E (mag.) 45.0 ft. "S14, NBT"
 Declination 1°20' West. W. Pine 9 N69°W (mag.) 28.3 ft. "S10, NBT"
- Witnesses for Corner 10:** W. Pine 10 S58°E (mag.) 28.7 ft. "1/16S, BT"
 Declination 2°15' West. W. Pine 8 N27°E (mag.) 31.1 ft. "1/16S, BT"
- Witnesses for Corner 15:** Tamarack 7 S46°W (mag.) 25.4 ft. "1/16S, BT"
 Declination 1°15' West. Tamarack 5 N 7°W (mag.) 11.6 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 5, 1979
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

