

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	MARQUETTE COUNTY LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 46 N. R. 29 X W.	I-4
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	, T. 46 N. R. 29 X W.	3 & 8
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I4 (1/4 corner between Sections 10 & 11, T46N, R29W):

- Cedar post (Not found. No subsequent monuments found.)
- Cedar 12 N23E 35 (Not found. No subsequent accessories found.)
- Cedar 5 S40E 10 (Not found. No subsequent accessories found.)

**Corner 3 (North 1/16 corner between Sections 10 & 11, T46N, R29W) and
Corner 8 (West 1/16 corner on E & W 1/4 line of Section 11, T46N, R29W):**

Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I4: Restored 9/5/78 on line between Sec. Cor. 10, 11, 14, & 15 and Sec. Cor. 2, 3, 10, & 11, at a position 40.000 ch. N of the former. The latter corner is less certain of being at or near the original position, and as natural features and a line tree stump in the south half of this section line agree with the 40.000 ch. position, I restored the corner accordingly.

Corner 3: Established 9/5/78 on line between 1/4 cor. 20.2755 ch. S and Sec. Cor. 20.2755 ch. N.

Corner 8: Established 8/29/78 on true E & W 1/4 line 20.060 ch. E of W 1/4 corner and 20.060 ch. W of Center 1/4 corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all 3 corners: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

- Witnesses for Corner I4: Cedar 10 S79°W (mag.) 19.9 ft. "1/4S, NBT"
- Declination 2°20' West. Cedar 7 S38°E (mag.) 17.6 ft. "1/4S, NBT"
- Witnesses for Corner 3: B. Spruce 6 N42°E (mag.) 45.9 ft. "1/16S, BT"
- Declination 1°30' West. B. Spruce 5 S89°E (mag.) 44.8 ft. "1/16S, BT"
- Witnesses for Corner 8: Tamarack 6 N 3°W (mag.) 35.5 ft.
- Declination 1°35' West. Tamarack 5 S47°W (mag.) 40.9 ft.

Note: These two trees have regular blazes, but are not scribed. Lower blazes have stake tacks driven into their faces.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 15, 1979

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

