

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	MARQUETTE COUNTY LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 46 N. <del>X</del> S., R. 29 <del>X</del> W.	J-3
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	, T. 46 N. <del>X</del> S., R. 29 <del>X</del> W.	2
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Corner J3 (1/4 corner between Sections 2 & 11, T46N, R29W):**  
 Cedar post (Not found. No subsequent monuments found.)  
 W. Pine 12 N17E 5 (Not found. No subsequent accessories found.)  
 Cedar 6 S32W 22 (Not found. No subsequent accessories found.)

**Corner 2 (East 1/16 corner between Sections 2 & 11, T46N, R29W):**  
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**Corner J3:** Restored 8/2/78 on line between Sec. Corners 40.1125 ch. to E and to W.  
 Corner falls on west side of a N & S oriented hill, about 25 lks. E of a swamp edge.

**Corner 2:** Established 8/29/78 on line between Sec. Cor. 20.056 ch. E and 1/4 cor. 20.056 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Corner J3:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 6 N23°E (mag.) 25.9 ft. "1/4S, NBT"  
 W. Birch 14 S81°W (mag.) 3.3 ft. "1/4S, NBT"  
 W. Birch 16 S48°E (mag.) 12.7 ft. "1/4S, NBT"  
 Distances horizontal. Declination is 1°40' West.

**Corner 2:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Tamarack 6 S72°W (mag.) 24.8 ft. "1/16S, BT"  
 Tamarack 5 N12°E (mag.) 24.0 ft. "1/16S, BT"  
 Declination is 2°10' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 15, 1979  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

