

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 46 N. X. R. 29 W.	I-3
2. PROPERTY CONTROLLING IN SECTION 11 _____	T. 46 N. X. R. 29 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 13 (Section Corner 2, 3, 10, & 11, T46N, R29W):
 Spruce post (Not found. Found 2 old wood post points.)
 Tamarack 6 S13 1/2 W 21 (Not found. No subsequent accessories found.)
 Tamarack 4 N15 E 23 (Not found. No subsequent accessories found.)

Corner 1 (West 1/16 corner between Sections 2 & 11, T46N, R29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 13: On 8/2/78 replaced the 2 post points with monument described in C, below. Points were old, but not possible to tell if either is from original post. Position checks with swamp edge to E, but not to S; distance E to original NE cor. Section 11 is consistent with distance along S boundary of Sec. 11. Position has been used by others, as an old brushed survey line runs N from it.

Corner 1: Established 9/5/78 on line between 1/4 cor. 20.056 ch. E and Sec. Cor. 20.056 ch. W.

Note: See sketch on reverse side for additional information.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 13: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Tamarack 6 N75°E (mag.) 46.8 ft. "S2, NBT"
 Tamarack 5 S36°E (mag.) 37.5 ft. "S11, NBT"
 Declination is 1°35' West.

Corner 1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Tamarack 9 S2 1/2° E (mag.) 50.7 ft. "1/16S, BT"
 W. Birch 14 N47° E (mag.) 15.7 ft. "1/16S, BT"
 Declination is 1°55' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Arthur O. Enger MICHIGAN REGISTERED LAND SURVEYOR DATE March 15, 1989

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

