

✓

**MICHIGAN**  
**DEPARTMENT OF CONSERVATION**  
**FORESTRY DIVISION**

**LAND CORNER RECORD**

T 45-46 NR 29 W

Marquette

COUNTY

DESCRIPTION OF CORNER --- Meander corner between Sections 2 and 35 on West side  
of Long Lake.

DESCRIPTION OF CORNER MONUMENT -----

WITNESSES TO CORNER --- 5" Tamarack --- N 83 E 15 Links, (N.C. HBT) ---

5" Tamarack --- N 2 W 6 1/2 Links, (N.C. HBT) ---

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.**

This corner was replaced from two Tamarack E.T.'s bearing N 25 W, 50 Links and  
S 22 1/2 W, 10 Links. Both E.T.'s down and badly rotted. Found scribe marks and  
overgrowth on both stumps.

Corner placed, witnessed and found with Forestry Division Survey Crew on  
28 July 1958.

**SURVEYORS SEAL**

SIGNED

*Billy D. Buckler*

Billy D. Buckler

REGISTERED LAND SURVEYOR

DATE

4-30-59