

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	(MARQUETTE COUNTY) LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 46 N. X R. 29 K. W.	#L-11
2. PROPERTY CONTROLLING IN SECTION <u>25</u>	T. 46 N. X R. 29 K. W.	#14
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 10, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner L-11 (1/4 corner between Sections 25 & 36, T46N, R29W):**
 Spruce post (Not found. No subsequent monuments found.)
 Spruce 10 N 4E 35 (Not found. No subsequent accessories found.)
 Spruce 6 S39W 37 (Not found. No subsequent accessories found.)
- Corner 14 (South 1/16 corner between Sections 25 & 30, T46N, R28-29W):**
 Not established in original survey and by approximation only, subsequently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner L-11: Restored on line between Sec. Cor. 39.8525 ch. East and Sec. Cor. 39.8525 ch. W. Found a 6" B. Spruce blazed on 4 sides for an approx. cor., S51-1/2°W 53.2 ft.**
- Corner 14: Established on line between Sec. Cor. 20.035 ch. S and 1/4 cor. 20.035 ch. N. Found a 2" x 2" x 5' squared post, purporting to be this corner, S75°W 9.6 ft., but as there was no 1/4 cor. nor sec. cor. N of it, it is hard to see how it could be anything but approximate.**
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner L-11: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.**
 Cedar 10 S89°W (mag.) 65.3 ft. "1/4S, NBT"
 Cedar 7 N21°W (mag.) 59.9 ft. "1/4S, NBT"
 Declination 1° 40' West.
- Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.**
 Tamarack 10 S 8° W (mag.) 76.2 ft. "1/16S, BT"
 J. Pine 7 N48°E (mag.) 35.0 ft. "1/16S, BT"
 Declination 1° 25' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

